



The panel has been tested to the Heavy Grade loading requirements of the PSA MOB PF2 PS/SPU March 1992 "Platform Floors (Raised Access Floors) Performance Specification"

С

B

N

Ε

S

- The panel has been subjected to seven point loads of 4.5kN for 24 hours and a UDL load of 12kN/m<sup>2</sup> for 24 hours
- The panel has been subjected to three times safety factor loads at the same positions. The point loading being 13.5kN and the UDL 36kN/m<sup>2</sup> all maintained for 5 minutes

